

ADDENDUM #1

Stonegate Trail Culvert Replacement

City of Perry City Hall
1211 Washington Street
Perry, GA 31069

Bids Due: **June 26, 2025 @ 2:00p**
Pre-Bid Meeting: **June 17, 2025 @ 2:00p (Required)**
Cost of Plans: Hard Copy -
Electronic Copy - \$25.00
ISE Project #: 1013.2403
Owner Contract No.: 2025-35
Date:

INCORPORATE CHANGES INTO THE CONTRACT DOCUMENTS AS DESCRIBED BELOW AND ATTACHED TO THIS ADDENDUM:

1. Will a traffic control plan be provided or described? Will permanent road closure signage be required? Will TP III Barricades with ROAD CLOSED signage attached be required? Will there be a waiting period before the road can be closed?

Answer: The contract requires the submission of an appropriate plan, as specified in Section 01 55 26 Traffic Control, that complies with all applicable Georgia Department of Transportation (DOT) requirements.

2. There are two paving typical section on sheet C-701. Which one is to be used for this project?

Answer: Use the paving section titled "Typical Paving & 24" Conc. Rollover Curb & Gutter." It includes 6" of GAB and 2" asphalt surface course.

3. On the initial ESPC plan on sheet C-510 the construction exit south of the site is shown with temporary pipe in the stream diversion. Will a dimension and material of these pipes be provided? Can this construction exit be deleted and only use the North exit?

Answer: The dimensions and material will not be provided. This is a construction means and methods item that is at the contractor's discretion. Yes, this can be deleted, and only use the North exit.

4. Is the downstream rock necessary?

Answer: Yes

5. It appears that temporary measures will be required to keep the 24" longitudinal storm drain system working until the culvert is completed and final storm drains, and end treatments can be placed. Include this in the bid?

Answer: Please include the cost of keeping these in service as part of line item 13 demolition.

6. Should the 2 longitudinal drains stop at the wingwalls?

Answer: Yes

7. To confirm the City of Perry wants the RCP but not any portion of the brick wingwalls? Is the contractor responsible for any damage to the RCP during its removal?

Answer: The city does not want any portion of the brick headwalls. It will be the contractor's responsibility to haul them away. The contractor is not responsible for any damage to the existing RCP during its removal. The contractor will be required to remove the four existing 48" RCP culverts and deliver them to 500 Ball Street in Perry. Perry will be responsible for unloading them once they arrive at 500 Ball Street.

8. What type of headwalls will be required for the proposed 18" and 24" HDPE culverts?

Answer: These headwalls should follow GDOT detail 1120 as shown on drawing sheet number C-701

9. Can you provide the existing asphalt depth?

Answer: The depth is unknown.

10. Are we to assume there will be No. 57 stone underneath all the box culverts, and apron?

Answer: Yes. Assume a 12" thick layer of No. 57 stone under all these structures. Include the cost of this stone in Line Item 15 for the culverts and 16 for the aprons.

11. What is the location of the bid opening?

Answer: The location of the bid opening will not be at City Hall as previously indicated. It will be at the exact location where we held the pre-construction conference. City of Perry administration building at 1211 Washington Street.