



Where Georgia comes together.

## **Bid 2025-28 Kings Chapel Sidewalk Replacement - ADDENDUM ONE**

DATE: March 31, 2025

PROJECT: Kings Chapel Sidewalk Replacement  
Bid 2025-28

This addendum supersedes and supplements all portions of the bid documents for the above referenced project.

Where any item called for in the requirement is supplemented hereby, the original requirements shall remain in effect.

Where any original item is amended, voided, or superseded hereby, the provision of such item not so specifically amended, voided, or superseded shall remain in effect.

---

### **Addendum**

Section 1.2 "Scope of Work" is amended to include the following:

1. There are two dumpster locations that must be reinforce with a minimum of 10 guage wire mesh
  - a. Location 1: approximately 200 Sq. Ft. of driveway & sidewalk
  - b. Location 2: approximately 200 Sq. Ft. of sidewalk (5' x 40')
2. The asphalt driveway at Whitney Manor is to remain in place. Only the sidewalk in this area is to be replaced
3. The pavers are to be set in wet mortar with no sand base
4. Paver accents should be installed every twelve feet and spacing at driveway areas should have the same spacing as if pavers where installed in driveway. **Pavers are not to be installed in driveways.**
5. There is no Crush and Run required. Existing subgrade should be compacted
6. A total of 26 ADA mats are to be wet set. Locations will be identidge on site at commencement of project

*Receipt of this addendum should be acknowledged on the Bid Form. It is the bidder's responsibility to ensure that they have all applicable addenda prior to Bid Submittal.*

END OF ADDENDUM